

Decommissioning: Technical Aspects and Management of Risks

More than just a project

Veronika Ustohalova


Exploratory Seminar: Decommissioning, a new challenge for nuclear safety
Brussels, 6 February 2017



Agenda

- 1** Technical basis
- 2** Decommissioning activities
- 3** Decommissioning strategies
- 4** Risk management
- 5** Conclusions



Technical basis of nuclear decommissioning: radioactive release under control



– Achieve a state without limitations – “below any release limit” – removal of construction.

Mechanisms of radioactive contamination

– Release from Pressurised water reactor: controlled area



uranium-235 or Plutonium-239) into fission to keep the fission process steady ⇒
 contained in surrounding non-radioactive materials and
 move in their whole.

corrosion and abraded activated particles
 which dissolve in cooling liquid and

Operation time and decommissioning complexity

Longer reactor operation time accumulates more contaminated radioactive material

- More fuel
- Higher neutron activation of reactor internals and the bio shield
- Deeper contamination of surfaces and structures
- Higher risk of internal release events - cause additional contamination of locations and materials to be cleaned-up

Europe's old nuclear power plants

Reactors connected to the network for at least 30 years, as of August 2015



Decommissioning activities


Challenge to remove activated and contaminated material and safely dispose; involves sophisticated technologies:

- Removing radioactive equipment and contamination from surface of selected materials
- Sorting all materials according to their (measured) degree of activation/contamination
- Cutting, solidifying or compacting those materials and package the materials
- Proper radioactive waste treatment and management:
 - The relevant space for the flow of waste (esp. radioactive) must be preplanned
 - Disposal under defined conditions involving interim storage and final disposal strategy



Decision on decommissioning strategy: pros and contras

- Decision on decommissioning strategy - immediate or deferred dismantling (allowing activity decline), entombment - and the relevant time line must consider all radiological risks and determines the decommissioning plan development.
- Use of work force knowledge diminish with postponing.
- Entombment as a last resort only in special cases (no recommended by IAEA)
- Further generation burden to be avoided.



Adapted acc. M. Knaack 2012


The terms ‘risk’ and ‘project management’ within decommissioning

- Decommissioning phase differs from the operational phase: it requires different organization structure, workforce, work planning.
- *Risk* in broad sense: identifying all aspects with potential to negatively influence the decommissioning performance (critical flow path).
- Project and risk management comparable with construction, but construction knowledge and works differs significantly: no construction to be newly developed but to be “discovered” how the construction developed in the past.
- Respective risk management system (RMS): series of arrangements for early detections, analyzing, evaluating and limiting risks of different kinds + solution analysis.
- Integral part of RM is risk communication culture.

Organizational aspect	Construction	Deconstruction/Dismantling	Operation
Project management	Crucial: to plan far ahead, to understand complex interactions, to understand consequences, to create optimized flows, to manage experiences, to fit plans to changes		Scarcely necessary: major refitting of the facility or outage planning and control
Risk management	Crucial: to understand all technical, organisational and financial risks in respect to their consequences for the critical flow path, risk communication culture necessary		Small relevance: Limited scope and uncertainties, most risks known

Risk management as integral part of decommissioning plan

- Risk management governs the whole planning process of the decommissioning project and should be incorporated within the overall management structure.
- RMS considers technical, organizational and financial risks with respect to their consequences for the critical flow path.



Missing or insufficient RM and/or RM wrongly implemented in to the management structure

dangerously affects the successful decommissioning implementation

Conclusions

- Decision on decommissioning strategy should consider all risk over long term.
- Sophisticated technologies developed but every reactor is a “special case”.
- Radiological risks associated with pre-planned longer time delays are considerable; the expectation to achieve cost reductions is highly doubtful: no workforce/ no knowledge, extended works (e.g. problematic decontamination)
- Considerable delays beyond responsibility towards future generations, entombment not recommended also by IAEA and should be a last resort.

The term risk in nuclear decommissioning:

No risk = ~~no~~ fun!

Contact

Veronika Ustohalova, Ph.D.

Senior Researcher

Öko-Institut e.V.

Nuclear Engineering & Facility Safety Division

Rheinstrasse 95

64295 Darmstadt

Germany

v.ustohalova@oeko.de

Tel.: +49 (0) 6151 819151

Homepage: <http://www.oeko.de/en/>

Thank you for your attention!

Do you have any questions?

